IN THE COURT OF THE MUNSIFF OF SHIMOGA.

Notice dated the 8th July 1905.

Wanted three candidates for apprentice clerks newly sanctioned, one alone getting Rs. 10 a month. None but Matriculates need apply.

K. LAKSHMINARAYANIAH, *Munsiff.*

TUMKUR DIVISION.

Dated 6th July 1905.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 31st July 1905, for restoring Chikka Malur Tank, Registered No. 218 of Maddagiri Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1906.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for Chikka Malur Tank," in default of which tenders will be rejected.

5. The first acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Description of work.	*Per*	*Quantity.*
Bund R. L. 56·00—		
Earthwork, watering and tampering, etc., as per specification	C. yd.	13,688
Stone work, new	,,	1,541
Stone work, old, dismantling and re-building with new jelly	,,	265
Grade stones including index and bed slab including fixing and numbering.	No.	43
B. M. stone	,,	2
Register	,,	1
Guage stone	,,	1
Date stone	,,	1
Turfing	S. yds.	11,253
Sluice R. L. 41·00—		
Earthwork	C. yd.	158
Brick in surki mortar	C. ft.	1,047
Surki plastering	Sqr.	7·22
Burnt stone slabs	S. ft.	277
Cutting holes in slab for arifice	Lump sum.	
Plug and rod, etc., complete	No.	1
Iron pipe sluice to feed the smaller tank including masonary works at R. L. 43·00.	Lump sum.	
Waste weir R L. 50·25—		
Burnt brick in chunam	C. ft.	2,933
Burnt stone in mortar, wings to right cross bund	,,	546
Burnt stone slabs	S. ft.	719
Chunam plastering	Sqr.	1·50
Rough stone revetment to weir and wing bund, etc.	C. yd.	266
Lowering the old right weir to R. L. 48·00 and clearing draft and approaches for extending it to 121 feet long.	Lump sum.	
Provision for lowering left old weir by 3 feet	Lump sum.	

C. MADAVA RAO, *Executive Engineer.*